



***Enduring Resources***

475 17<sup>TH</sup> Street Suite 1500 Denver Colorado 80202  
Telephone 303 573-1222 Fax 303 573 0461

September 12, 2006

Utah Division of Oil, Gas and Mining  
1594 West North Temple, Suite 1210  
P. O. Box 145801  
Salt Lake City, Utah 84114-5801

Attn.: Ms. Diana Whitney

RE: Enduring Resources, LLC  
Archy Bench 10-22-34-36  
SWSE 36-10S-22E  
State Lease: ML-49959  
Uintah County, Utah

Dear Ms. Whitney:

Enclosed are two original applications to drill concerning the above-referenced proposed well. This information was also submitted to SITLA.

Enduring Resources, LLC is requesting the Utah Division of Oil, Gas and Mining to hold this application and all future information as confidential.

If any questions arise or additional information is required, please contact me at 303-350-5719

Very truly yours,

**ENDURING RESOURCES, LLC**  
Evette Bissett  
Regulatory Compliance Assistant

Enclosures

cc: SITLA w/ attachments

**RECEIVED**

**SEP 14 2006**

**DIV. OF OIL, GAS & MINING**

**STATE OF UTAH**  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 3

AMENDED REPORT ☐  
(highlight changes)

<b>APPLICATION FOR PERMIT TO DRILL</b>				5. MINERAL LEASE NO: ML-49959	6. SURFACE: State
1A. TYPE OF WORK:    DRILL <input checked="" type="checkbox"/> REENTER <input type="checkbox"/> DEEPEN <input type="checkbox"/>				7. IF INDIAN, ALLOTTEE OR TRIBE NAME:	
B. TYPE OF WELL:    OIL <input type="checkbox"/> GAS <input checked="" type="checkbox"/> OTHER _____    SINGLE ZONE <input type="checkbox"/> MULTIPLE ZONE <input checked="" type="checkbox"/>				8. UNIT or CA AGREEMENT NAME:	
2. NAME OF OPERATOR: Enduring Resources, LLC				9. WELL NAME and NUMBER: Archy Bench 10-22-34-36	
3. ADDRESS OF OPERATOR: 475 17th St., Ste 1500    CITY Denver    STATE CO    ZIP 80220			PHONE NUMBER: (303) 350-5719		
4. LOCATION OF WELL (FOOTAGES)  AT SURFACE: 755' FSL - 2210' FEL    637981X    39.900251 AT PROPOSED PRODUCING ZONE:    4417723Y    -109.385966 Same				10. FIELD AND POOL, OR WILDCAT: <del>Unsubsidized</del> Natural Gas	
11. QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWSE 36 10S 22E				12. COUNTY: Uintah	
14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE: 40.3 Southeast of Bonanzal, UT				13. STATE: UTAH	
15. DISTANCE TO NEAREST PROPERTY OR LEASE LINE (FEET) 755'		16. NUMBER OF ACRES IN LEASE: 1360		17. NUMBER OF ACRES ASSIGNED TO THIS WELL: 40 acres	
18. DISTANCE TO NEAREST WELL (DRILLING, COMPLETED, OR APPLIED FOR) ON THIS LEASE (FEET) 1000' +		19. PROPOSED DEPTH: 8,063		20. BOND DESCRIPTION: RLB0008031	
21. ELEVATIONS (SHOW WHETHER DF, RT, GR, ETC.): 5753'    RT-KB		22. APPROXIMATE DATE WORK WILL START: 12/1/2006		23. ESTIMATED DURATION: 20 days	

24. PROPOSED CASING AND CEMENTING PROGRAM							
SIZE OF HOLE	CASING SIZE, GRADE, AND WEIGHT PER FOOT			SETTING DEPTH	CEMENT TYPE, QUANTITY, YIELD, AND SLURRY WEIGHT		
20"	14"	line pipe		40	3 yards	Ready Mix	
11"	8-5/8"	J-55	24#	2,016	Premium Lead	138 sxs	3.50 11.1
					Premium Tail	138 sxs	1.15 15.8
7-7/8"	4-1/2"	N-80	11.6#	8,063	Class G	152 sxs	3.3 11.0
					50/50 Poz Class G	841 sxs	1.56 14.3

25. ATTACHMENTS

VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES:

<input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER	<input checked="" type="checkbox"/> COMPLETE DRILLING PLAN
<input checked="" type="checkbox"/> EVIDENCE OF DIVISION OF WATER RIGHTS APPROVAL FOR USE OF WATER	<input type="checkbox"/> FORM 5, IF OPERATOR IS PERSON OR COMPANY OTHER THAN THE LEASE OWNER

NAME (PLEASE PRINT) Evette Bissett    TITLE Regulatory Compliance Assistant

SIGNATURE *Evette Bissett*    DATE 9/11/2006

(This space for State use only)

**Approved by the  
Utah Division of  
Oil, Gas and Mining**

API NUMBER ASSIGNED: 43-047-38605

APPROVAL:

Date: 05-14-07  
By: *[Signature]*


**RECEIVED**

SEP 14 2006

DIV. OF OIL, GAS & MINING

**T10S, R22E, S.L.B.&M.**


**ENDURING RESOURCES**



WELL LOCATION, ARCHY BENCH  
10-22-34-36, LOCATED AS SHOWN IN  
THE SW 1/4 SE 1/4 OF SECTION 36,  
T10S, R22E, S.L.B.&M. UTAH COUNTY,  
UTAH.



THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS  
PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS  
MADE BY ME OR UNDER MY SUPERVISION AND THAT  
THE SAME ARE TRUE AND CORRECT TO THE BEST OF  
MY KNOWLEDGE AND BELIEF. No. 189377



1922  
Brass  
Cap

**TRI STATE LAND SURVEYING & CONSULTING**  
180 NORTH VERNAL AVE. - VERNAL, UTAH 84078  
(435) 781-2501

DATE DRAWN: 8-17-05	SURVEYED BY: C.M.	<b>SHEET 2a OF 10</b>
REVISED:	DRAWN BY: F.T.M.	
NOTES:	SCALE: 1" = 1000'	

◆ = SECTION CORNERS LOCATED  
BASIS OF ELEV; U.S.G.S. 7-1/2 min  
QUAD (ARCHY BENCH)

**ENDURING RESOURCES, LLC**

425 Seventeenth Street, Suite 1500

Denver, Colorado 80202

Telephone: 303-573-1222

Facsimile: 303-573-0461

September 12, 2006

State of Utah  
Division of Oil, Gas and Mining  
P.O. Box 145801  
Salt Lake City, Utah 84114-5801

Attention: Ms. Diana Whitney

**RE: Exception Well Location  
Archy Bench 10-22-34-36  
SWSE Section 36-T10S-R22E  
755' FSL - 2210 FEL  
Lease Serial No.: UTU-49959  
Uintah County, Utah**

Dear Ms. Whitney:

Enduring Resources, LLC ("ERLLC") plans to drill the above-referenced well from an exception location to limit surface impact and drilling on steep slopes.

ERLLC is the only leasehold interest owner within 460 feet of any part of the above-referenced proposed well's proposed well bore, therefore,

*A. ERLLC also grants itself permission for an exception well location.*

In the event there are any other outstanding matters preventing these APD's from being approved, please let me know at your earliest convenience, 303-350-5719 ([ebissett@enduringresources.com](mailto:ebissett@enduringresources.com))

Very truly yours



**ENDURING RESOURCES, LLC**  
Evette Bissett  
Regulatory Compliance Assistant

**RECEIVED**

**SEP 14 2006**

**DIV. OF OIL, GAS & MINING**

Enduring Resources, LLC  
Archy Bench 10-22-34-36  
SWSE 36-T10S-R22E  
Uintah County, Utah  
State Lease: ML-49959

**ONSHORE ORDER 1 - DRILLING PLAN**

**1. Estimated Tops of Geological Markers:**

Formation	Depth (K.B.)
Uinta	Surface
Green River	901
Wasatch	3853
Mesaverde	5948

**2. Estimated Depths of Anticipated Water, Oil, Gas or Other Minerals:**

Substance	Formation	Depth (K.B.)
	KB-Uinta Elevation: 5753'	
Oil / Gas	Green River	901
Oil /Gas	Wasatch	3853
Oil /Gas	Mesaverde	5948
	Estimated TD	8063

A 11" hole will be drilled to approximately 2000 feet. The depth will be determined by the depth that the Birds Nest zone is encountered. The hole will be drilled 400 feet beyond the top of the Birds Nest zone and surface casing will be set.

**3. Pressure Control Equipment: (3000 psi schematic attached)**

- A. Type: Eleven (11) inch double gate hydraulic BOP with eleven (11) inch annular preventer on 3,000 psi casinghead, with 3,000 psi choke manifold equipped per the attached diagram. BOPE as specified in *Onshore Oil & Gas Order Number 2*. A PVT, stroke counter and flow sensor will be installed to check for flow and monitor pit volume.
- B. Pressure Rating: 3,000 psi BOPE
- C. Kelly will be equipped with upper and lower Kelly valves.
- D. Testing Procedure: Annular Preventer

At a minimum, the annular preventer will be pressure tested to 50% of the stack rated working pressure for a period of ten (10) minutes or until provisions of the test are met, whichever is longer.

At a minimum, the above pressure test will be performed:

1. When the annular preventer is initially installed;
2. Whenever any seal subject to test pressure is broken;
3. Following related repairs; and
4. At thirty (30) day intervals.

In addition to the above, the annular preventer will be functionally operated at least weekly.

#### Blow-Out Preventer

At a minimum, the BOP, choke manifold, and related equipment will be pressure tested to the approved working pressure of the BOP stack (if isolated from the surface casing by a test plug) or to 70% of the internal yield strength of the surface casing (if the BOP is not isolated from the casing by a test plug). Pressure will be maintained for a period of at least ten (10) minutes or until the requirements of the test are met, whichever is longer.

At a minimum, the above pressure test will be performed:

1. When the BOP is initially installed;
2. Whenever any seal subject to test pressure is broken;
3. Following related repairs; and
4. At thirty (30) day intervals.

In addition to the above, the pipe and blind rams will be activated each trip, but not more than once each day. All BOP drills and tests will be recorded in the IADC driller's log.

#### E. Miscellaneous Information:

The blowout preventer and related pressure control equipment will be installed, tested and maintained in compliance with the specifications in and requirements of *Onshore Oil & Gas Order Number 2*.

#### 4. Proposed Casing & Cementing Program:

##### A. Casing Program: All New

Hole Size	Casing Size	Wt./Ft.	Grade	Joint	Depth Set (MD)
20"	14" O.D.				40' (GL)
11"	8-5/8"	24#	J-55	ST&C	0 – 2,016' (KB) est.
7-7/8"	4-1/2"	11.6#	N-80	LT&C	0 – 8063' (KB)

The surface casing will have guide shoe, 1 joint, insert float collar. Centralize the shoe joint with bowspring centralizers in the middle and top of the joint and the next 16 joints

with bowspring centralizers on every other collar (8 centralizers total). Thread lock guide shoe.

Casing string(s) will be pressure tested to 0.22 psi/foot of casing string length or 1500 psi, whichever is greater (not to exceed 70% of the internal yield strength of the casing), after cementing and prior to drilling out from under the casing shoe.

**B. Casing Design Parameters:**

Depth (MD)	Casing	Collapse(psi)/SF	Burst (psi)/SF	Tension(mlbs)/SF
40' (GL)	14" OD			
2016' (KB)	8-5/8", 24#/ft, J55, STC	1370/1.52(a)	2950/3.28(b)	244/5.81(c)
8063' (KB)	4-1/2", 11.6#/ft, N-80, LTC	6350/1.52 (d)	7780/2.02 (e)	223/2.77(f)

- (a.) based on full evacuation of pipe with 8.6 ppg fluid on annulus
- (b.) based on 8.6 ppg gradient with no fluid on annulus
- (c.) based on casing string weight in 8.6 ppg mud
- (d.) based on full evacuation of pipe with 10.0 ppg fluid on annulus
- (e.) based on 9.2 ppg gradient, gas to surface, with no fluid on annulus, no gas gradient
- (f.) based on casing string weight in 9.2 ppg mud

**PROPOSED CEMENTING PROGRAM**

**Surface Casing (if well will circulate)-Cemented to surface**

CASING	SLURRY	FT. of FILL	CEMENT TYPE	SXS	EXCESS (%)	WEIGHT (ppg)	YIELD (ft <sup>3</sup> /sx)
8-5/8"	Lead	1516	Premium cement + 16% gel + 0.25 pps celloflake	138	25%	11.1	3.50
8-5/8"	Tail	500	Premium cement + 2% CaCl <sub>2</sub> + 0.25 pps celloflake	138	25%	15.8	1.15

A cement top job is required if cement fallback is greater than 10' below ground level. Top job (weight 15.8 ppg, yield 1.15 ft<sup>3</sup>/sx) cement will be premium cement w/ 3% CaCl<sub>2</sub>.+0.25 pps celloflake. Volume as required

**Surface Casing (if well will not circulate) - Cemented to surface**

CASING	SLURRY	FT. of FILL	CEMENT TYPE	SXS	EXCESS (%)	WEIGHT (ppg)	YIELD (ft <sup>3</sup> /sx)
8-5/8"	Lead	500	Premium cement + 2% CaCl <sub>2</sub> + 0.25 pps celloflake	138	25	15.8	1.15
8-5/8"	Top job	As req.	Premium cement + 3% CaCl <sub>2</sub> + 0.25 pps celloflake	As Req.		15.8	1.15

**Production Casing and Liner** - Cemented TD to 300' above base of surface casing

CASING	SLURRY	FT. of FILL	CEMENT TYPE	SXS	EXCESS (%)	WEIGHT (ppg)	YIELD (ft <sup>3</sup> /sx)
4-1/2"	Lead	1737	Class "G" + 5% NaCl + 12% Gel + 0.25 pps celloflake + 0.2% antifoam + 0.25% fluid loss + 1% extender	152	25	11.0	3.3
4-1/2"	Tail	4610	50/50 POZ Class G + 2% gel +1% CaCl <sub>2</sub> + 0.2% dispersant + 0.2% fluid loss + 0.1% antifoam	841	25	14.3	1.56

Cement volumes for the 4-1/2" Production Casing will be calculated to provide a top of cement to 300' above base of surface casing. Cement volumes are approximate and were calculated under the assumption that a gauge hole will be achieved. Actual cement volumes may vary due to variations in the actual hole size and will be determined by running a caliper log on the drilled hole. Actual cement types may vary due to hole conditions and cement contractor used.

All waiting on cement (WOC) times will be adequate to achieve a minimum of 500 psi compressive strength at the casing shoe prior to drilling out.

5. **Drilling Fluids (mud) Program:**

Interval (MD)	Mud Weight	Fluid Loss	Viscosity	Mud Type
0' – 2016' (KB)		No cntrl		Air/mist
2000'-3000' (KB)	8.4-8.6	No cntrl	28-36	Water
3000'-8063' (KB)	8.8-9.8	8 - 10 ml	32-42	Water/Gel

Sufficient mud material(s) to maintain mud properties, control lost circulation and contain a blowout will be available at the well site during drilling operations.

6. **Evaluation Program:**

Tests: No tests are currently planned.

Coring: No cores are currently planned.

Samples: No sampling is currently planned.



## Logging

- Dual Induction – SFL /Gamma Ray/Caliper/SP/TDLT/CNL/ML  
TD to Base Surface Casing
- Cement Bond Log / Gamma Ray:  
TD to Base of Surface Casing or Top of Cement if below Base of Surface Casing

Stimulation: A stimulation or frac treatment will be designed for completion of this well based on openhole log analysis. The drill site, as approved, will be sufficient size to accommodate all completion activities.

## 7. Abnormal Conditions:

No abnormal temperatures or pressures are anticipated. No H<sub>2</sub>S has been encountered or known to exist from previous wells drilled to similar depths in the general area.

Maximum anticipated bottom hole pressure equals approximately 4193 psi (calculated at 0.52psi/foot of hole) and maximum anticipated surface pressure equals approximately 2419 psi (anticipated bottom hole pressure minus the pressure of a partially evacuated hole calculated at 0.22 psi/foot of hole).

## 8. Anticipated Starting Dates:

- Anticipated Commencement Date- Within one year of APD issue.
- Drilling Days- Approximately 10 days
- Completion Days - Approximately 10 days
- Anticipate location construction within 30 days of permit issue.

## 9. Variances:

None anticipated

## 10. Other:

A Cultural Resource Inventory and Paleontology reconnaissance shall be conducted for the well location, access route and pipeline. The reports shall be submitted to the Division of Oil, Gas and Mining and the School and Institutional Trust lands Administration upon their receipt.

Single Shot directional surveys will be dropped every 2000 feet to monitor hole angle.

### **Directions to the Archy Bench 10-22-34-36 Well Pad**

Beginning at the city of Bonanza, Utah. Leave the city of Bonanza heading south on state highway 45 for a distance of approximately 5.7 miles where there is a turn-off to the right. Turn right, leaving state highway 45, and proceed southwest for a distance of approximately 5.1 miles (3.2 + 1.9 as shown on Topo "A"). The road then turns to the west; proceed northwesterly along said road for a distance of approximately 3.7 miles. Said road then turns to the southwest; proceed southwesterly then westerly for a distance of approximately 3.2 miles where the road forks. Turn left and bear southerly along the Asphalt Wash road for a distance of 3.0 miles where the road forks near a landing strip. Stay right, and continue heading south along the West Fork road for a distance of approximately 6.5 miles where there is a turn-off to the right. Turn right and bear westerly for a distance of approximately 1.7 miles. The road then turns to the north; proceed northerly along said road for a distance of approximately 3.8 miles where there is a turn-off to the left. Turn left and bear northwest for a distance of approximately 1.4 miles where there is a fork in the road near a landing strip. Turn right and bear northerly for a distance of approximately 2.1 miles where the said road turns and bears southwest. Continue along said road as it turns and bears southwest and continue bearing southwest for a distance of approximately 1.5 miles. The road then turns to the north; proceed northerly for a distance of approximately 1.4 miles where there is a turn-off to the left onto proposed access. Turn left and bear northwesterly along proposed access for a distance of approximately 6,555' (about 1.2 mi.) to the Proposed Archy Bench 10-22-34-36.

# **Enduring Resources, LLC**

## **Archy Bench 10-22-34-36**

SWSE 36-10S-22E

Uintah County, Utah

State Lease: ML-49959

### **MULTI-POINT SURFACE USE & OPERATIONS PLAN**

#### **1. Existing Roads:**

Beginning at the city of Bonanza, Utah, leave the city of Bonanza heading south on state highway 45 for a distance of approximately 5.7 miles where there is a turn-off to the right. Turn right, leaving state highway 45, and proceed southwest for a distance of approximately 5.1 miles (3.2 + 1.9 as shown on Topo "A"). The road then turns to the west; proceed northwesterly along said road for a distance of approximately 3.7 miles. Said road then turns to the southwest; proceed southwesterly then westerly for a distance of approximately 3.2 miles where the road forks. Turn left and bear southerly along the Asphalt Wash road for a distance of 3.0 miles where the road forks near a landing strip. Stay right, and continue heading south along the West Fork road for a distance of approximately 6.5 miles where there is a turn-off to the right. Turn right and bear westerly for a distance of approximately 1.7 miles. The road then turns to the north; proceed northerly along said road for a distance of approximately 3.8 miles where there is a turn-off to the left. Turn left and bear northwest for a distance of approximately 1.4 miles where there is a fork in the road near a landing strip. Turn right and bear northerly for a distance of approximately 2.1 miles where the said road turns and bears southwest. Continue along said road as it turns and bears southwest and continue bearing southwest for a distance of approximately 1.5 miles. The road then turns to the north; proceed northerly for a distance of approximately 1.4 miles where there is a turn-off to the left onto proposed access. Turn left and bear northwesterly along proposed access for a distance of approximately 6,555' (about 1.2 mi.) to the Proposed Archy Bench 10-22-34-36.

#### **2. Planned Access Roads:**

The proposed access road will be approximately 6,555 feet of new construction, of which 600 feet is on-lease and 5,955 feet are on Federal Lease #UTU66407. **BLM Right-of-Way for access has been applied for and approved.**

The proposed access road will be utilized to transport personnel, equipment and supplies to and from the proposed well site during drilling, completion and production operations. The road will be utilized year round.

The access road will be crowned 2% to 3%, ditched and constructed with a running surface of 18 feet and a maximum disturbed width of 30 feet right-of-way. Maximum grade of road is 5% or less. Graveling or capping the roadbed will be performed as necessary to provide a well constructed, safe road. No fence crossings, culverts, turnouts, cattle guards or major cuts and fills are required. Prior to construction or upgrading, the proposed road shall be cleared of any snow and allowed to dry completely.

Surface disturbance and vehicular traffic will be limited to the proposed location and proposed access route. Any additional area needed will be approved in advance. All construction shall be in conformance with the standards outlined in the BLM and Forest Service publication: Surface Operating Standards for Oil and Gas Exploration and Development. 1989.

The road surface and shoulders will be kept in a safe usable condition and will be maintained in accordance with the original construction standards. All drainage ditches will be kept clear and free flowing and will be maintained according to original construction standards. The access road surface will be kept free of trash during operations. All traffic will be confined to the approved disturbed surface. Road drainage crossings shall be designed so they will not cause siltation or accumulation of debris in the drainage crossing nor shall the drainages be blocked by the road bed. Erosion of drainage ditches by runoff water shall be prevented by diverting water off at frequent intervals by means of cutouts. Upgrading shall not be allowed during muddy conditions. Should mud holes develop, they shall be filled in and detours around them avoided. When snow is removed from the road during the winter months, the snow shall be pushed outside of the borrow ditches and the turnouts kept clear so that snowmelt will be channeled away from the road.

3. **Location of Existing Wells within a One-Mile radius (See "Topo" Map "C" attached):**

The following wells are wells located within a one (1) mile or greater radius of the proposed location.

- |    |       |                                    |
|----|-------|------------------------------------|
| a. | None: | Water Wells:                       |
| b. | None: | Injection Wells:                   |
| c. | (6):  | Producing Wells:                   |
|    |       | 1. State 1022-36E, SWNW 36         |
|    |       | 2. Rock House 4-36, NWNW 36        |
|    |       | 3. Rock House 11-36, NESW 36       |
|    |       | 4. Rock House 10-22-14-36, SWSW 36 |
|    |       | 5. Rock House 10-22-13-36, NWSW 36 |
|    |       | 6. Rock House 11-31, NESW 31       |
| d. | (6):  | Drilling Wells:                    |
|    |       | 1. Rock House 2D-36, NWNE 36       |
|    |       | 2. Rock House 10-22-42-36, NENW 36 |
|    |       | 3. Rock House 10-22-4-36, NWNE 36  |
|    |       | 4. Rock House 10-22-33-36, SWNE 36 |
|    |       | 5. Rock House 10-22-32-36, SWNE 36 |
|    |       | 6. Rock House 10-22-21-36, NENW 36 |
| e. | None: | Shut-in Wells:                     |
| f. | None: | Temporarily Abandoned Wells:       |
| g. | None: | Disposal Wells:                    |
| h. | (1):  | Abandoned Wells:                   |
|    |       | 1. Sharples-Texaco St 1, NESW 36   |
| i. | None: | Dry Holes:                         |
| j. | None: | Observation Wells:                 |

k. (11):

Pending (staked) Wells:

1. There are eleven other wells staked within a one mile radius of this well

**4. Location of Existing and/or Proposed Facilities:**

All production facilities will be located on the disturbed portion of the well pad and at a minimum of 25 feet from the toe of the back slope or the top of the fill slope.

A dike will be constructed completely around those production facilities which contain fluids (i.e. production tanks, produced water tanks and/or heater treater). These dikes will be constructed of compacted subsoil, be impervious, hold 100% of the capacity of the largest tank and be independent of the back cut.

All permanent (on site for six months or longer) above the ground structures constructed or installed, including pumping units, will be painted a flat, non-reflective, earth tone color to match one of the standard environmental colors, as determined by the Rocky Mountain Five State Inter-Agency Committee

All facilities will be painted within 6 months of installation. The color shall be designated by DOG&M and SITLA. Facilities required to comply with the Occupational Safety and Health Act (OSHA) will be excluded.

Any necessary pits will be properly fenced to protect livestock and prevent wildlife entry.

Gas Gathering Pipeline for this well will be:

15'	Surface Pipeline	On-Lease	SITLA
-0-	Surface Pipeline	Off-Lease	n/a

If this well is capable of economic production, a 4" (or less) steel surface gas gathering line and related equipment shall be installed. The surface gas gathering line shall be in use year round. A total of approximately less than 15 feet of surface gas gathering pipeline shall be laid on the surface to minimize surface disturbance:

The proposed pipeline will begin at the well site; and be laid on the surface next to the new access road to tie-in to a steel surface pipeline that is located next to the county road.

The meter run will be housed. The gas gathering line will be buried or anchored down from the wellhead to the meter.

Upon plugging and abandonment, the gas gathering line will be removed and the disturbed area will be re-contoured and restored as near as practical to the original condition. If necessary, re-seeding operations will be performed after completion of other reclamation operations.

5. **Location and Type of Water Supply:**

Whenever practical, water will be obtained from Enduring Resources LLC Water Right Number 49-2215 or Water Right Number 49-2216 (\*See Townships of permitted Use below). If those sources are not available, a new water source shall be submitted prior to commencing operations. (These permits have one-year terms and then must be renewed)

\*Enduring Water Permits' Townships of Use:

<b><u>T10S-R22E</u></b>	T11S-R22E	T12S-R22E
T10S-R23E	T11S-R23E	T12S-R23E
T10S-R24E	T11S-R24E	T12S-R24E

Water will be hauled to the location over the roads marked on "Topo" Maps "A" and "B."

No water well is to be drilled on this lease.

6. **Source of Construction Materials:**

Surface and subsoil materials in the immediate area will be utilized for location and access road construction.

Any gravel will be obtained from a commercial source; however, gravel sized rock debris associated with location and access road construction may be used as access road surfacing material.

7. **Methods of Handling Waste Materials:**

Drill cuttings will be contained and buried in the reserve pit.

Drilling fluids, including salts and chemicals, will be contained in the reserve pit will be removed and disposed of at an approved waste disposal facility within 120 days after drilling is terminated.

The reserve pit will be constructed on the location and will not be located within natural drainage, where a flood hazard exists or surface runoff will destroy or damage the pit walls. The reserve pit will be constructed so that it will not leak, brake or allow discharge of liquids.

The reserve pit will be lined with ¼ felt and a minimum of 16 mm plastic with sufficient bedding used to cover any rocks. The liner will overlap the pit walls and be covered with dirt and/or rocks to hold it in place. No trash or scrap that could puncture the will be disposed of in the pit.

A chemical portable toilet will be furnished with the drilling rig. The toilet will be replaced periodically utilizing a licensed contractor to transport by truck the portable chemical toilet so that its contents can be delivered to the Vernal Wastewater Treatment Facility in accordance with state and county regulations.

Garbage, trash and other waste materials will be collected in a portable, self-contained, fully enclosed trash cage during operations. No trash well is burned on location.

All debris and other waste material not contained in the trash cage will be cleaned up and removed from the location immediately after removal of the drilling rig.

Any open pits will be fenced during the operations. The fencing will be maintained until such time as the pits are backfilled.

No chemicals subject to reporting under SARA Title III (hazardous materials) in an amount greater than 10,000 pounds will be used, produced, stored, transported or disposed of in association with the drilling, completion or testing of this well. Furthermore, no extremely hazardous substances, as defined in 40 CFR 355, in threshold planning quantities, will be used, produced, stored, transported or disposed of in association with the drilling, completion or testing of this well.

Produced oil will be stored in an oil tank and then hauled by truck to a crude purchaser facility. Any produced water from the proposed well will be contained in a water tank and will then be hauled by truck to an approved disposal site.

**8. Ancillary Facilities:**

During drilling operations, approximately 20 days, the site will be a manned camp. Three or four additional trailers will be on location to serve as the crews' housing and eating facilities. These will be located on the perimeter of the pad site within the topsoil stockpiles. Refer to Sheet 4.

**9. Well Site Layout: (Refer to Sheets #2, #3, and #4)**

The attached Location Layout Diagrams described drill pad cross-sections, cuts and fills and locations of the mud tanks, reserve pit, flare pit, pipe racks, trailer parking, spoil dirt stockpile(s) and surface material stockpiles(s).

Please see the attached diagram for rig orientation and access roads.

The top soil will be windrowed rather than piled. It will be reseeded and track walker at the time the location is constructed. Seeding will be with the determined during the onsite. (Refer to "Seed Mixture for Windrowed Top Soil Will included:" following herein.

The top soil removed from the pit area will be store separately and will not be reseeded until the pit is reclaimed.

All pits shall be fence to the following minimum standards:

- a. 39 inch net wire shall be used with at least one strand of barbed wire on top of the net wire. Barbed wire is not necessary if pipe or some type of reinforcement rod is attached to the top of the entire fence.
- b. The net wire shall be no more than 2 inches above the ground. The barbed wire shall be 3 inches over the new wire. Total height of the fence shall be at least 42 inches.

- c. Corner posts shall be cemented and/or braced in such a manner to keep the fence tight at all times.
- d. Standard steel, wood or pipe posts shall be used between the corner braces. Maximum distance between any two fence posts shall be no greater than 16 feet.
- e. All wire shall be stretched by, using a stretching device, before it is attached to corner posts.
- f. The reserve pit fencing will be on three sides during drilling operations and on the fourth side when the rig moves off location. Pits will be fenced and maintained until cleanup.
- g. The reserve pit fencing will be on three sides during drilling operations and on the fourth side when the rig moves off location. Pits will be fenced and maintained until cleanup.
- h. Location size may change prior to drilling the well due to the current rig availability. If the proposed location is not large enough to accommodate the drilling, the location will be re-surveyed and a Form 9 will be submitted.

# **10. Plans for Surface Reclamation:**

## **Producing Location:**

- a. Immediately upon well completion the location and surrounding area will be cleared of all unused tubing, equipment, materials, trash and debris not required for production.
- b. Immediately upon well completion any hydrocarbons in the pit shall be removed in accordance with 40CFR 3162.7.
- c. Before any dirt work associated with location restoration takes place, the reserve pit shall be as dry as possible. All debris in it will be removed. Other waste and spoil materials will be disposed of immediately upon completion of operations.
- d. The reserve pit and that portion of the location not needed for production facilities/operations will be re-contoured to the approximated natural contours. The reserve pit will be reclaimed within 90 days from the date of well completion, weather permitting.
- e. To prevent surface water(s) from standing (ponding) on the reclaimed reserve pit area, final reclamation of the reserve pit will consist of "mounding" the surface 3 feet above surrounding round surface to allow the reclaimed pit area to drain effectively.
- f. Upon completion of back filling, leveling and re-contouring, the stockpiled topsoil will be spread evenly over the reclaimed area(s).

## **Dry Hole/Abandoned Location:**

- i. Abandoned well sites, roads and other disturbed areas will be restored as nearly as practical to their original condition. Where applicable, these conditions include the re-establishment of irrigation systems, the re-establishment of appropriate soil conditions and re-establishment of vegetation as specified.
- ii. All disturbed surfaces will be re-contoured to the approximated natural contours with reclamation of the well pad and access road to be performed as soon as practical after final abandonment. If necessary, re-seeding operations will be performed after completion of other reclamation operations.



**Seed Mixture for Windrowed Top Soil Will Included:**

To be provided by the DOG&M and/or SITLA.

**11. Surface Ownership: Location, Access and Pipeline Route:**

Wellsite: SITLA

Access: SITLA and BLM with approved ROW

Pipeline: SITLA

**12. Other Information**

**On-site Inspection for Location, Access and Pipeline Route:**

The on-site will be scheduled by SITLA and DOG&M.

**Special Conditions of Approval:**

- Tanks and Production Equipment shall be painted pursuant of SITLA and DOG&M.
- Surface Gathering Pipeline shall be 4" or less

**Archeology:**

- a. A Cultural Resource Inventory Report is pending and to be prepared by Montgomery Archaeological Consultants.

**Paleontology:**

- a. A Paleontology Reconnaissance Report is pending and to be prepared by Intermountain Paleo-Consulting.

If, during operations, any archaeological or historical sites, or any objects of antiquity (subject to the Antiquities Act of June 8, 1906) are discovered, all operations which would affect such sites will be suspended and the discovery reported promptly to the surface management agency.

13. **Lessee's or Operator's Representatives:**

**Representatives:**

Alvin R. (Al) Arlian  
Landman – Regulatory Specialist  
Enduring Resources, LLC  
475 17<sup>th</sup> Street, Suite 1500  
Denver, Colorado 80202  
Office Tel: 303-350-5114  
Fax Tel: 303-573-0461  
[aarlian@enduringresources.com](mailto:aarlian@enduringresources.com)

Teme Singleton  
Drilling Engineer  
Enduring Resources, LLC  
475 17<sup>th</sup> Street, Suite 1500  
Denver, Colorado 80202  
Office Tel: 303-573-5711  
Fax Tel: 303-573-0461  
[tsingleton@enduringresources.com](mailto:tsingleton@enduringresources.com)

# ENDURING RESOURCES


## WELL PAD INTERFERENCE PLAT

ARCHY BENCH 10-22-34-36

ARCHY BENCH 10-22-44-36

ARCHY BENCH 10-22-43-36

Section 36, T10S, R22E, S.L.B.&M.




### TOP HOLE FOOTAGES

10-22-34-36  
755' FSL & 2210' FEL

10-22-44-36  
774' FSL & 2205' FEL

10-22-43-36  
793' FSL & 2201' FEL



### BOTTOM HOLE FOOTAGES

10-22-34-36  
VERTICAL

10-22-44-36  
657' FSL & 664' FEL

10-22-43-36  
1972' FSL & 663' FEL

### Note:

Bearings are  
Based on G.L.O.

### RELATIVE COORDINATES From top hole to bottom hole

WELL	NORTH	EAST
34-36	N/A	N/A
44-36	-122'	1,541'
43-36	1,174'	1,542'

### LATITUDE & LONGITUDE Surface position of Wells (NAD 83)

WELL	LATITUDE	LONGITUDE
34-36	39° 54' 00.68"	109° 23' 12.28"
44-36	39° 54' 00.87"	109° 23' 12.26"
43-36	39° 54' 01.07"	109° 23' 12.25"

SURVEYED BY: C.M. DATE DRAWN: 8-17-05

DRAWN BY: F.T.M. SCALE: 1" = 60'

NOTES:


**Tri State**  
Land Surveying, Inc.  
180 NORTH VERNAL AVE. VERNAL, UTAH 84078

(435) 781-2501

SHEET  
3  
OF 10

# ENDURING RESOURCES

ARCHY BENCH 10-22-34-36, 10-22-44-36 & 10-22-34-36  
SECTION 36, T10S, R22E, S.L.B.&M.



SURVEYED BY: C.M. DATE DRAWN: 8-17-05  
DRAWN BY: F.T.M. SCALE: 1" = 60'  
NOTES:





Tri State  
Land Surveying, Inc.  
180 NORTH VERNAL AVE. VERNAL, UTAH 84078  
(435) 781-2501

SHEET  
4  
OF 10

# ENDURING RESOURCES

## CROSS SECTIONS

ARCHY BENCH 10-22-34-36, 10-22-44-36 & 10-22-34-36



NOTE:  
UNLESS OTHERWISE NOTED  
ALL CUT/FILL SLOPES ARE  
AT 1.5:1

### ESTIMATED EARTHWORK QUANTITIES (No Shrink or swell adjustments have been used) (Expressed in Cubic Yards)

ITEM	CUT	FILL	6" TOPSOIL	EXCESS
PAD	13,940	13,940	Topsoil is not included in Pad Cut	0
PIT	5,390	0		5,390
TOTALS	19,330	13,940	2,150	5,390

SURVEYED BY: C.M. DATE DRAWN: 8-17-05

DRAWN BY: F.T.M. SCALE: 1" = 60'

NOTES:


**Tri State** (435) 781-2501  
Land Surveying, Inc.  
180 NORTH VERNAL AVE. VERNAL, UTAH 84078

SHEET  
5  
OF 10

# ENDURING RESOURCES

## TYPICAL RIG LAYOUT

ARCHY BENCH 10-22-34-36, 10-22-44-36 & 10-22-34-36




Note:  
Flare pit is to be located at least 100' from well head.

SURVEYED BY: C.M.	DATE DRAWN: 8-17-05
DRAWN BY: F.T.M.	SCALE: 1" = 60'
NOTES:	

**Tri State**  
Land Surveying, Inc.  
180 NORTH VERNAL AVE. VERNAL, UTAH 84078  
(435) 781-2501

SHEET  
6  
OF 10





ENDURING RESOURCES

**Archy Bench 10-22-34-36**  
**Sec. 36, T10S, R22E, S.L.B.&M.**



**Tri-State**  
*Land Surveying Inc.*  
 (435) 781-2501  
 180 North Vernal Ave. Vernal, Utah 84078

SCALE: 1" = 100,000'

DRAWN BY: bgm

DATE: 08-19-2005

**Legend**

- Existing Road
- Proposed Access


TOPOGRAPHIC MAP

**"A"**

SHEET

**7**  
OF 10





ENDURING RESOURCES

**Archy Bench 10-22-34-36**  
**Sec. 36, T10S, R22E, S.L.B.&M.**



**Tri-State**  
*Land Surveying Inc.*  
 (435) 781-2501

180 North Vernal Ave. Vernal, Utah 84078

SCALE: 1" = 2,000'

DRAWN BY: bgm

DATE: 09-02-2005

**Legend**

Existing Road  
 Proposed Access

TOPOGRAPHIC MAP


**"B"**

SHEET

**8**

OF 10





**ENDURING RESOURCES**

**Archy Bench 10-22-34-36**  
**Sec. 36, T10S, R22E, S.L.B.&M.**



**Tri-State**  
*Land Surveying Inc.*  
 (435) 781-2501  
 180 North Vernal Ave. Vernal, Utah 84078

**SCALE: 1" = 2,000'**  
**DRAWN BY: bgm**  
**DATE: 08-19-2005**

**Legend**

- Location
- One-Mile Radius

**TOPOGRAPHIC MAP**


**"B"**

**SHEET**

**9**

**OF 10**





**ENDURING RESOURCES**

**Archy Bench 10-22-34-36**  
**Sec. 36, T10S, R22E, S.L.B.&M.**



**Tri-State**  
*Land Surveying Inc.*  
 (435) 781-2501  
 180 North Vernal Ave. Vernal, Utah 84078

**SCALE: 1" = 2,000'**

**DRAWN BY: bgm**

**DATE: 08-22-2005**

**Legend**

- Roads
- Existing Gas Line
- Proposed Gas Line

**TOPOGRAPHIC MAP**

**"D"**

**SHEET**

**10**

**OF 10**





**CENTER STAKE**

Date Photographed: 08/19/2005

Date Drawn: 08/22/2005

Drawn By: bgm

**LOOKING SW  
ACCESS**



ENDURING RESOURCES

**A.B. 10-22-34-36**



*Tri-State  
Land Surveying Inc.*

(435) 781-2501

160 North Vernal Ave. Vernal, Utah 84078





NORTH

  
**ENDURING RESOURCES**  
**A.B. 10-22-34-36**

Date Photographed: 08/19/2005  
Date Drawn: 08/22/2005  
Drawn By: bgm

  
**Tri-State**  
*Land Surveying Inc.*  
(435) 781-2501  
180 North Vernal Ave. Vernal, Utah 84078

EAST







SOUTH

  
ENDURING RESOURCES

A.B. 10-22-34-36

Date Photographed: 08/19/2005

Date Drawn: 08/22/2005

Drawn By: bgm

  
*Tri-State*  
*Land Surveying Inc.*  
(435) 781-2501  
180 North Vernal Ave. Vernal, Utah 84078

WEST



**WORKSHEET**  
**APPLICATION FOR PERMIT TO DRILL**

APD RECEIVED: 09/14/2006

API NO. ASSIGNED: 43-047-38605

WELL NAME: ARCHY BENCH 10-22-34-36

OPERATOR: ENDURING RESOURCES, LLC ( N2750 )

PHONE NUMBER: 303-350-5719

CONTACT: EVETTE BISSETT

**PROPOSED LOCATION:**

SWSE 36 100S 220E

SURFACE: 0755 FSL 2210 FEL

BOTTOM: 0755 FSL 2210 FEL

COUNTY: Uintah

LATITUDE: 39.90025 LONGITUDE: -109.3860

UTM SURF EASTINGS: 637981 NORTHINGS: 4417723

FIELD NAME: NATURAL BUTTES ( 630 )

INSPECT LOCATN BY: / /		
Tech Review	Initials	Date
Engineering	DW	12/1/06
Geology		
Surface		

LEASE TYPE: 3 - State

LEASE NUMBER: ML-49959

PROPOSED FORMATION: MVRD

SURFACE OWNER: 3 - State

COALBED METHANE WELL? NO

**RECEIVED AND/OR REVIEWED:**

☒ Plat  
☒ Bond: Fed[] Ind[] Sta[] Fee[]  
(No. RLB0008031 )  
☒ Potash (Y/N)  
☒ Oil Shale 190-5 (B) or 190-3 or 190-13  
☒ Water Permit  
(No. 49-2215 )  
☒ RDCC Review (Y/N)  
(Date: )  
☒ Fee Surf Agreement (Y/N)  
☒ Intent to Commingle (Y/N)

**LOCATION AND SITING:**

\_\_\_ R649-2-3.  
Unit: \_\_\_\_\_  
\_\_\_ R649-3-2. General  
Siting: 460 From Qtr/Qtr & 920' Between Wells  
☒ R649-3-3. Exception  
\_\_\_ Drilling Unit  
Board Cause No: \_\_\_\_\_  
Eff Date: \_\_\_\_\_  
Siting: \_\_\_\_\_  
\_\_\_ R649-3-11. Directional Drill

COMMENTS:

*Needs Permit (11-21-2006)*

STIPULATIONS:

*1- Spacing Strip  
2- STATEMENT OF BASIS  
3- OIL SHALE  
4- Surface Csg Cont Strip*



# Application for Permit to Drill

## Statement of Basis

11/27/2006

Utah Division of Oil, Gas and Mining

Page 1

<b>APD No</b>	<b>API WellNo</b>	<b>Status</b>	<b>Well Type</b>	<b>Surf Owner</b>	<b>CBM</b>
118	43-047-38605-00-00		GW	S	No
<b>Operator</b>	ENDURING RESOURCES, LLC		<b>Surface Owner-APD</b>		
<b>Well Name</b>	ARCHY BENCH 10-22-34-36		<b>Unit</b>		
<b>Field</b>	NATURAL BUTTES		<b>Type of Work</b>		
<b>Location</b>	SWSE 36 10S 22E S 0 FL 0 FL GPS Coord (UTM) 637981E 4417723N				

### Geologic Statement of Basis

Enduring proposes to set 2,016 feet of surface casing cemented to the surface. The base of the moderately saline water is estimated at 4,400 feet. A search of Division of Water Rights records shows no water wells within a 10,000 foot radius of the proposed location. The surface formation at this location is the Uinta/Green River Formation transition. The Uinta Formation is made up of discontinuous sands interbedded with shales and are not expected to produce prolific aquifers. The Green River Formation is made up of interbedded limestones, shales and sandstones. Fresh water aquifers can be found in the Green River Formation and should be protected. The proposed surface casing should adequately protect any potentially useable aquifers. Production casing cement should be brought up above the base of the moderately saline ground water.

Brad Hill  
APD Evaluator

11/27/2006  
Date / Time

### Surface Statement of Basis

Both the surface and minerals of the proposed Archy Bench 10-22-34-36 gas well are owned by SITLA. Three wells are planed from this location. The location is approximately 18 miles southerly of Bonanza Ut, and approximately 66 miles southwest of Vernal, UT.

Topography in the general area is broad canyon bottoms separated by steep and often ledgey side-slopes, which top out onto ridge tops. Frequent outwash plains and deposits occur along the sides of the major bottoms. The drainages of Asphalt Wash are broad somewhat gentle alluvial washes, which are dry except for spring runoff and sometimes-intense summer rainstorms. The Asphalt Wash drainages collectively run northerly to the White River about 3 miles to the north.

The proposed location is near the end of a long narrow ridge which ends high above the junction of two major draws which join and drain into the White River. At the location the ridge is sloping to the north in broken terrain. The pad is laid out at a right angle to the ridge and will serve for 3 wells. Approximately 6,555 feet of access road will be constructed to reach the location. The integrity of the pit liner must be insured during this well and for other directional wells planned from this location.

The location appears to be the best and possibly the only site for drilling wells in the area.

Floyd Bartlett  
Onsite Evaluator

11/21/2006  
Date / Time

### Conditions of Approval / Application for Permit to Drill

<b>Category</b>	<b>Condition</b>
Pits	A synthetic liner with a minimum thickness of 16 mils with a felt subliner shall be properly installed and maintained in the reserve pit.



# **ON-SITE PREDRILL EVALUATION**

## **Utah Division of Oil, Gas and Mining**

**Operator** ENDURING RESOURCES, LLC  
**Well Name** ARCHY BENCH 10-22-34-36  
**API Number** 43-047-38605-0 **APD No** 118 **Field/Unit** NATURAL BUTTES  
**Location:** 1/4,1/4 SWSE **Sec** 36 **Tw** 10S **Rng** 22E 0 FL 0 FL  
**GPS Coord (UTM)** 637974 4417735 **Surface Owner**

### **Participants**

Floyd Bartlett (DOGM), Doug Hammond (Enduring Resources), Larry Rowell (Ponderosa Construction), Jim Davis (SITLA), Ben Williams (UDWR)

### **Regional/Local Setting & Topography**

The proposed Achhy Bench 10-22-34-36 gas well location is approximately 18 miles southerly of Bonanza Ut, and approximately 66 miles southwest of Vernal, UT.

Topography in the general area is broad canyon bottoms separated by steep and often ledgey side-slopes, which top out onto broad ridge tops. Frequent outwash plains and deposits occur along the sides of the major bottoms. The drainages of Asphalt Wash are broad somewhat gentle alluvial washes, which are dry except for spring runoff and sometimes-intense summer rainstorms. The Asphalt Wash drainages collectively run northerly to the White River about 3 miles to the north.

The proposed location is near the end of a long narrow ridge which ends above the junction of two major draws which join and drain into the White River. At the location the ridge is sloping to the north in broken terraine. The pad is laid out at a right angle to the ridge and will serve for 3 wells. Approximately 6,555 feet of access road will be constructed to reach the location.

### **Surface Use Plan**

#### **Current Surface Use**

Wildlife Habitat

#### **New Road**

<b>Miles</b>	<b>Well Pad</b>		<b>Src Const Material</b>	<b>Surface Formation</b>
1.2	<b>Width</b> 250	<b>Length</b> 355	Onsite	UNTA

**Ancillary Facilities** N

### **Waste Management Plan Adequate?** Y

### **Environmental Parameters**

**Affected Floodplains and/or Wetland** N

#### **Flora / Fauna**

End of the pinion-juniper type in black sage.

Deer, antelope, rabbits, coyotes and numerous small mammals and birds.

#### **Soil Type and Characteristics**

Stoney sandy loam.

**Erosion Issues** N

Sedimentation Issues N

Site Stability Issues N

Drainage Diversion Required N

Berm Required? N

Erosion Sedimentation Control Required? N

Paleo Survey Run? Y    Paleo Potential Observed? N    Cultural Survey Run? Y    Cultural Resources?

**Reserve Pit**

Site-Specific Factors		Site Ranking
Distance to Groundwater (feet)	>200	0
Distance to Surface Water (feet)	>1000	0
Dist. Nearest Municipal Well (ft)	>5280	0
Distance to Other Wells (feet)	>1320	0
Native Soil Type	Mod permeability	10
Fluid Type	Fresh Water	5
Drill Cuttings	Normal Rock	0
Annual Precipitation (inches)	<10	0
Affected Populations	<10	0
Presence Nearby Utility Conduits	Not Present	0
Final Score		15    2    Sensitivity Level

**Characteristics / Requirements**

The reserve pit is planned on the southwest side of the location in an area of cut. Dimensions are 170' x 215' x 12' deep. A liner is required. The liner must be properly installed and padded to insure no leakage occurs in this specific location.

Closed Loop Mud Required? N    Liner Required? Y    Liner Thickness 16    Pit Underlayment Required? Y

**Other Observations / Comments**

Ben Williams representing the Utah Division of Wildlife Resources stated the area is classified as limited value year-long range for deer and antelope. He recommends no restrictions for either of these species.

Floyd Bartlett  
Evaluator

11/21/2006  
Date / Time

Casing Schematic

BHP

$$0.052(8063)9.8 = 4109 \text{ psi}$$

anticipate 4193 psi

Gas

$$.12(8063) = 968$$

$$4109 - 968 = 3141 \text{ psi}$$

MASP

8-5/8"

MW 8.4

Frac 19.3

Wet

$$.22(8063) = 1774$$

$$\text{MASP} = 2335 \text{ psi}$$

BOPE = 3M

$$\text{Burst} = 2950 \text{ psi}$$

$$70\% = 2065 \text{ psi}$$

Max Prod csg. shoe

$$.22(6047) = 1330$$

$$4109 - 1330 = 2779 \text{ psi}$$

test - 2065 psi

✓ Stop ⇒ surf cont.

✓ Adequate OKD 02/1/06

4-1/2"  
MW 9.8

Production  
8063. MD

Unit TOC to surf. w/4% w/o

✓ stop

TOC @  
766.

+1840 TOC w/9% w/o

Surface  
2016. MD

TOC @  
2284.

+3853' Wasatch

+4400' ± BMSW

+5948' Mesaverde

Well name:	<b>2006-11 Enduring Archy Bench 10-22-34-36</b>	
Operator:	<b>Enduring Resources, LLC</b>	
String type:	Surface	Project ID: 43-047-38605
Location:	Uintah County, Utah	

**Design parameters:**
**Collapse**

Mud weight: 8.400 ppg  
Design is based on evacuated pipe.

**Minimum design factors:**
**Collapse:**

Design factor 1.125

**Burst:**

Design factor 1.00

**Environment:**

H2S considered? No  
Surface temperature: 75 °F  
Bottom hole temperature: 103 °F  
Temperature gradient: 1.40 °F/100ft  
Minimum section length: 1,000 ft

Cement top: 766 ft

**Burst**

Max anticipated surface pressure: 1,774 psi  
Internal gradient: 0.120 psi/ft  
Calculated BHP 2,016 psi

No backup mud specified.

**Tension:**

8 Round STC: 1.80 (J)  
8 Round LTC: 1.80 (J)  
Buttress: 1.60 (J)  
Premium: 1.50 (J)  
Body yield: 1.60 (B)

Tension is based on buoyed weight.  
Neutral point: 1,762 ft

**Non-directional string.**
**Re subsequent strings:**

Next setting depth: 8,063 ft  
Next mud weight: 9.800 ppg  
Next setting BHP: 4,105 psi  
Fracture mud wt: 19.250 ppg  
Fracture depth: 2,016 ft  
Injection pressure: 2,016 psi

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Est. Cost (\$)
1	2016	8.625	24.00	J-55	ST&C	2016	2016	7.972	10378

Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (kips)	Tension Strength (kips)	Tension Design Factor
1	880	1370	1.557	2016	2950	1.46	42.3	244	5.77 J

Prepared by: Helen Sadik-Macdonald  
Div of Oil, Gas & Minerals

Phone: 801/538-5357  
FAX: 801/359-3940

Date: November 30, 2006  
Salt Lake City, Utah

**Remarks:**

Collapse is based on a vertical depth of 2016 ft, a mud weight of 8.4 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

*Engineering responsibility for use of this design will be that of the purchaser.*

Well name:	<b>2006-11 Enduring Archy Bench 10-22-34-36</b>	
Operator:	<b>Enduring Resources, LLC</b>	
String type:	Production	Project ID: 43-047-38605
Location:	Uintah County, Utah	

**Design parameters:**
**Collapse**

Mud weight: 9.800 ppg  
Design is based on evacuated pipe.

**Minimum design factors:**
**Collapse:**

Design factor 1.125

**Burst:**

Design factor 1.00

**Environment:**

H2S considered? No  
Surface temperature: 75 °F  
Bottom hole temperature: 188 °F  
Temperature gradient: 1.40 °F/100ft  
Minimum section length: 1,000 ft

Cement top: 2,284 ft

**Burst**

Max anticipated surface pressure: 2,331 psi  
Internal gradient: 0.220 psi/ft  
Calculated BHP 4,105 psi

No backup mud specified.

**Tension:**

8 Round STC: 1.80 (J)  
8 Round LTC: 1.80 (J)  
Buttress: 1.60 (J)  
Premium: 1.50 (J)  
Body yield: 1.60 (B)

**Non-directional string.**

Tension is based on buoyed weight.  
Neutral point: 6,882 ft

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Est. Cost (\$)
1	8063	4.5	11.60	N-80	LT&C	8063	8063	3.875	33207

Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (kips)	Tension Strength (kips)	Tension Design Factor
1	4105	6350	1.547	4105	7780	1.90	79.8	223	2.79 J

Prepared by: Helen Sadik-Macdonald  
Div of Oil, Gas & Minerals

Phone: 801/538-5357  
FAX: 801/359-3940

Date: November 30, 2006  
Salt Lake City, Utah

**Remarks:**

Collapse is based on a vertical depth of 8063 ft, a mud weight of 9.8 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

*Engineering responsibility for use of this design will be that of the purchaser.*

**From:** Ed Bonner  
**To:** Mason, Diana  
**Date:** 5/11/2007 4:36 PM  
**Subject:** Well Clearance

**CC:** Davis, Jim; Garrison, LaVonne; Hill, Brad; Hunt, Gil

The following wells have been given cultural resources clearance by the Trust Lands Cultural Resources Group:

EnCana Oil & Gas (USA) Inc  
Middle Mesa State 36-24-29-24 (API 43 037 31856)

Enduring Resources, LLC  
Archy Bench 10-22-34-36 (API 43 047 38605)  
Asphalt Wash 11-24-41-16 (API 43 047 38768)

EOG Resources, Inc  
East Chapita 56-16 (API 43 047 39203)

Kerr McGee Oil & Gas Onshore LP  
NBU 1022-24I (API 43 047 39031)

Tidewater Oil & Gas Company, LLC  
Cactus Rose 36-43-2217 (API 43 019 31535)

If you have any questions regarding this matter please give me a call.



**State of Utah**

**Department of  
Natural Resources**

MICHAEL R. STYLER  
*Executive Director*

**Division of  
Oil, Gas & Mining**

JOHN R. BAZA  
*Division Director*

JON M. HUNTSMAN, JR.  
*Governor*

GARY R. HERBERT  
*Lieutenant Governor*

May 14, 2007

Enduring Resources, LLC  
475 17th St., Ste. 1500  
Denver, CO 80202

Re: Archy Bench 10-22-34-36 Well, 755' FSL, 2210' FEL, SW SE, Sec. 36,  
T. 10 South, R. 22 East, Uintah County, Utah

Gentlemen:

Pursuant to the provisions and requirements of Utah Code Ann. § 40-6-1 *et seq.*, Utah Administrative Code R649-3-1 *et seq.*, and the attached Conditions of Approval, approval to drill the referenced well is granted.

Appropriate information has been submitted to DOGM and administrative approval of the requested exception location is hereby granted.

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date. The API identification number assigned to this well is 43-047-38605.

Sincerely,

Gil Hunt  
Associate Director

pab  
Enclosures

cc: Uintah County Assessor  
SITLA

Operator: Enduring Resources, LLC  
Well Name & Number Archy Bench 10-22-34-36  
API Number: 43-047-38605  
Lease: ML-49959

Location: SW SE      Sec. 36      T. 10 South      R. 22 East

### Conditions of Approval

#### 1. General

Compliance with the requirements of Utah Admin. R. 649-1 *et seq.*, the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

#### 2. Notification Requirements

The operator is required to notify the Division of Oil, Gas and Mining of the following action during drilling of this well:

- 24 hours prior to cementing or testing casing – contact Dan Jarvis
- 24 hours prior to testing blowout prevention equipment – contact Dan Jarvis
- 24 hours prior to spudding the well – contact Carol Daniels
- Within 24 hours of any emergency changes made to the approved drilling program – contact Dustin Doucet
- Prior to commencing operations to plug and abandon the well – contact Dan Jarvis

The operator is required to get approval from the Division of Oil, Gas and Mining before performing any of the following actions during the drilling of this well:

- Plugging and abandonment or significant plug back of this well – contact Dustin Doucet
- Any changes to the approved drilling plan – contact Dustin Doucet

The following are Division of Oil, Gas and Mining contacts and their telephone numbers (please leave a voice mail message if the person is not available to take the call):

- Dan Jarvis at: (801) 538-5338 office  
(801) 942-0873 home
- Carol Daniels at: (801) 538-5284 office
- Dustin Doucet at: (801) 538-5281 office  
(801) 733-0983 home

#### 3. Reporting Requirements

All required reports, forms and submittals will be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.



4. Compliance with the State of Utah Antiquities Act forbids disturbance of archeological, historical, or paleontological remains. Should archeological, historical or paleontological remains be encountered during your operations, you are required to immediately suspend all operations and immediately inform the Trust Lands Administration and the Division of State History of the discovery of such remains.
5. In accordance with Order in Cause No. 190-5(b) dated October 28, 1982, the Operator shall comply with requirements of Rules R649-3-31 and R649-3-27 pertaining to Designated Oil Shale Areas. Additionally, the operator shall ensure that the surface and/or production casing is properly cemented over the entire oil shale interval as defined by Rule R649-3-31. The Operator shall report the actual depth the oil shale is encountered to the Division.
6. Compliance with the Conditions of Approval/Application for Permit to Drill outlined in the Statement of Basis. (Copy Attached)
7. This proposed well is located in an area for which drilling units (well spacing patterns) have not been established through an order of the Board of Oil, Gas and Mining (the "Board"). In order to avoid the possibility of waste or injury to correlative rights, the operator is requested, once the well has been drilled, completed, and has produced, to analyze geological and engineering data generated therefrom, as well as any similar data from surrounding areas if available. As soon as is practicable after completion of its analysis, and if the analysis suggests an area larger than the quarter-quarter section upon which the well is located is being drained, the operator is requested to seek an appropriate order from the Board establishing drilling and spacing units in conformance with such analysis by filing a Request for Agency Action with the Board.
8. Surface casing shall be cemented to the surface.

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

CONFIDENTIAL

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

5. LEASE DESIGNATION AND SERIAL NUMBER:  
ML-49959

6. IF INDIAN, ALLOTTEE OR TRIBE NAME:  
N/A

7. UNIT or CA AGREEMENT NAME:  
N/A

8. WELL NAME and NUMBER:  
Archy Bench 10-22-34-36

9. API NUMBER:  
4304738605

10. FIELD AND POOL, OR WILDCAT:  
Undesignated

1. TYPE OF WELL  
OIL WELL ☐ GAS WELL ☒ OTHER \_\_\_\_\_

2. NAME OF OPERATOR:  
Enduring Resources, LLC

3. ADDRESS OF OPERATOR:  
475 17th Street, Suite 1500 DENVER CO 80202

PHONE NUMBER:  
(303) 350-5114

4. LOCATION OF WELL

FOOTAGES AT SURFACE: 755' FSL - 2210' FEL

COUNTY: Uintah

QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWSE 36 10S 22E S

STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: 3/1/2008	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input checked="" type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion:	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: New Total Depth
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Enduring would like to drill this well deeper than set forth in the approved APD.

- Attached is a new proposed casing and cementing program, also
- Attached is a new drilling program for this increase in depth.

Utah State Bond #RLB0008031  
Operator No. N2750

Approved by the  
Utah Division of  
Oil, Gas and Mining

Date: 12/7/07  
By: [Signature]

RECEIVED

DEC 05 2007

DIV. OF OIL, GAS & MINING

NAME (PLEASE PRINT) Alvin R. (Al) Arlian

TITLE Landman - Regulatory Specialist

SIGNATURE [Signature]

DATE 12/3/2007

(This space for State use only)

PROPOSED CASING AND CEMENTING PROGRAM								
SIZE OF HOLE	CASING SIZE, GRADE, AND WEIGHT PER FOOT			SETTING DEPTH	CEMENT TYPE, QUANTITY, YIELD, AND SLURRY WEIGHT			
20"	14"	line pipe		40	3 yards	Ready Mix		
12-1/4"	9-5/8"	J-55	36#	2,016	Premium Lead	498 sxs	3.5	11.1
					Premium Tail	196 sxs	1.15	15.8
8-1/2"	7"	VHCP-11©	11.6#	9,000	Class G	94 sxs	3.3	11
					50/50 Poz Class G	635 sxs	1.56	14.3
7-7/8"	4-1/2"	N-80	13.5-15.1#	12,955	Class G	22 SXS	3.3	11
					50/50 Poz Class G	810 SXS	1.56	14.3

**Enduring Resources, LLC  
Arch Bench 10-22-34-36  
SWSE 36-10S-22E  
Uintah County, Utah  
Federal Lease: UTU-49959**

**ONSHORE ORDER 1 - DRILLING PLAN**

**1. Estimated Tops of Geological Markers:**

Formation	Depth (K.B.) (feet)
Uinta	Surface
Green River	901
Wasatch	3853
Mesaverde	5948
Mancos	8690
Morrison	12557

**2. Estimated Depths of Anticipated Water, Oil, Gas or Other Minerals:**

Substance	Formation	Depth (K.B.) (in feet)
	KB-Uinta Elevation: 5753'	
Oil / Gas	Green River	901
Oil /Gas	Wasatch	3853
Oil /Gas	Mesaverde	5948
Oil /Gas	Mancos	8690
Oil /Gas	Morrison	12557
	Estimated TD	12760

An 12 1/4" hole will be drilled to approximately 2016 feet. The depth will be determined by the depth that the Birds Nest zone is encountered. The hole will be drilled 400 feet beyond the top of the Birds Nest zone and surface casing will be set. Surface casing will be pre-set before drilling rig is moved on location.

**3. Pressure Control Equipment: (5000 psi schematic attached)**

- A. Type: Eleven (11) inch double gate hydraulic BOP with eleven (11) inch annular preventer on 5,000 psi casinghead, with 5,000 psi choke manifold equipped per the attached diagram. BOPE as specified in *Onshore Oil & Gas Order Number 2*. A PVT, stroke counter and flow sensor will be installed to check for flow and monitor pit volume.
- B. Pressure Rating: 5,000 psi BOPE

C. Kelly will be equipped with upper and lower Kelly valves.

D. Testing Procedure: Annular Preventer

At a minimum, the annular preventer will be pressure tested to 50% of the stack rated working pressure for a period of ten (10) minutes or until provisions of the test are met, whichever is longer.

At a minimum, the above pressure test will be performed:

1. When the annular preventer is initially installed;
2. Whenever any seal subject to test pressure is broken;
3. Following related repairs; and
4. At thirty (30) day intervals.

In addition to the above, the annular preventer will be functionally operated at least weekly.

#### Blow-Out Preventer

At a minimum, the BOP, choke manifold, and related equipment will be pressure tested to the approved working pressure of the BOP stack (if isolated from the surface casing by a test plug) or to 70% of the internal yield strength of the surface casing (if the BOP is not isolated from the casing by a test plug). Pressure will be maintained for a period of at least ten (10) minutes or until the requirements of the test are met, whichever is longer.

At a minimum, the above pressure test will be performed:

1. When the BOP is initially installed;
2. Whenever any seal subject to test pressure is broken;
3. Following related repairs; and
4. At thirty (30) day intervals.

In addition to the above, the pipe and blind rams will be activated each trip, but not more than once each day. All BOP drills and tests will be recorded in the IADC driller's log.

E. Miscellaneous Information:

The blowout preventer and related pressure control equipment will be installed, tested and maintained in compliance with the specifications in and requirements of *Onshore Oil & Gas Order Number 2*.

#### 4. **Proposed Casing & Cementing Program:**

##### A. Casing Program: All New

Hole Size	Casing Size	Wt./Ft.	Grade	Joint	Depth Set (MD)
20"	14" O.D.				40' (GL)
12 1/4"	9-5/8"	36#	J-55	ST&C	0 – 2,016' (KB) est.
8 1/2"	7"	26#	HCP-110	LT&C	0 – 9000' (KB)
6-1/4"	4-1/2"	13.5# & 15.1#	N-80	LT&C	0 – 12760' (KB)

The surface casing will have guide shoe. Centralize the shoe joint with bowspring centralizers in the middle and top of the joint and the next 16 joints with bowspring centralizers on every other collar (8 centralizers total). Thread lock guide shoe. Surface casing will be pre-set before drilling rig is moved on location.

Casing string(s) will be pressure tested to 0.22 psi/foot of casing string length or 1500 psi, whichever is greater (not to exceed 70% of the internal yield strength of the casing), after cementing and prior to drilling out from under the casing shoe.

##### B. Casing Design Parameters:

Depth (MD)	Casing	Collapse(psi)/SF	Burst (psi)/SF	Tension (mlbs)/SF
40' (GL)	14" OD			
2016' (KB)	9-5/8", 36#/ft, J55, STC	2020/2.24(a)	3520/3.91(b)	394/6.25(c)
9000' (KB)	7", 26#/ft, N-80, LTC	6230/1.27(d)	9960/2.32 (e)	522/2.60(f)
12760 (KB)	4-1/2", 13.5-15.1#/ft, N-80, LTC	11080/2.26(d)	10480/2.44 (e)	247/2.11(f)

- (a.) based on full evacuation of pipe with 8.6 ppg fluid on annulus
- (b.) based on 8.6 ppg gradient with no fluid on annulus
- (c.) based on casing string weight in 8.6 ppg mud
- (d.) based on full evacuation of pipe with 10.0 ppg fluid on annulus
- (e.) based on 9.2 ppg gradient, gas to surface, with no fluid on annulus, no gas gradient
- (f.) based on casing string weight in 9.2 ppg mud

#### **PROPOSED CEMENTING PROGRAM**

##### **Surface Casing (if well will circulate)-Cemented to surface**

CASING	SLURRY	FT. of FILL	CEMENT TYPE	SXS	EXCESS (%)	WEIGHT (ppg)	YIELD (ft <sup>3</sup> /sx)
9-5/8"	Lead	1516	Premium cement + 16% gel + 0.25 pps celloflake	498	25%	11.1	3.50
9-5/8"	Tail	500	Premium cement + 2% CaC <sub>2</sub> + 0.25 pps celloflake	200	25%	15.8	1.15

A cement top job is required if cement fallback is greater than 10' below ground level. Top job (weight 15.8 ppg, yield 1.15 ft<sup>3</sup>/sx) cement will be premium cement w/ 3% CaCl<sub>2</sub>.+0.25 pps celloflake. Volume as required

**Surface Casing (if well will not circulate) - Cemented to surface**

CASING	SLURRY	FT. of FILL	CEMENT TYPE	SXS	EXCESS (%)	WEIGHT (ppg)	YIELD (ft <sup>3</sup> /sx)
9-5/8"	Lead	500	Premium cement + 2% CaCl <sub>2</sub> + 0.25 pps celloflake	196	25	15.8	1.15
9-5/8"	Top job	As req.	Premium cement + 3% CaCl <sub>2</sub> + 0.25 pps celloflake	As Req.		15.8	1.15

**Intermediate Casing - Cemented TD to 300' above base of surface casing**

CASING	SLURRY	FT. of FILL	CEMENT TYPE	SXS	EXCESS (%)	WEIGHT (ppg)	YIELD (ft <sup>3</sup> /sx)
7"	Lead	2994	Class "G" + 5% NaCl + 12% Gel + 0.25 pps celloflake + 0.2% antifoam + 0.25% fluid loss + 1% extender	94	25	11.0	3.3
7"	Tail	4885	50/50 POZ Class G + 2% gel +1% CaCl <sub>2</sub> + 0.2% dispersant + 0.2% fluid loss + 0.1% antifoam	635	25	14.3	1.56

**Production Casing - Liner - Cemented TD to 300' above base of Intermediate Casing**

CASING	SLURRY	FT. of FILL	CEMENT TYPE	SXS	EXCESS (%)	WEIGHT (ppg)	YIELD (ft <sup>3</sup> /sx)
4 1/2"	Lead	300	Class "G" + 5% NaCl + 12% Gel + 0.25 pps celloflake + 0.2% antifoam + 0.25% fluid loss + 1% extender	22	25	11.0	3.3
4-1/2"	Tail	3469	50/50 POZ Class G + 2% gel +1% CaCl <sub>2</sub> + 0.2% dispersant + 0.2% fluid loss + 0.1% antifoam	810	25	14.3	1.56

Cement volumes for the 4-1/2" Production Casing will be calculated to provide a top of cement to 300' above base of Intermediate casing. Cement volumes are approximate and were calculated under the assumption that a gauge hole will be achieved. Actual cement volumes may vary due to variations in the actual hole size and will be determined by running a caliper log on the drilled hole. Actual cement types may vary due to hole conditions and cement contractor used.

All waiting on cement (WOC) times will be adequate to achieve a minimum of 500 psi compressive strength at the casing shoe prior to drilling out.

**5. Drilling Fluids (mud) Program:**

Interval (MD)	Mud Weight	Fluid Loss	Viscosity	Mud Type
0' – 2016' (KB)		No cntrl		Air/mist
2000'-3000' (KB)	8.4-8.6	No cntrl	28-36	Water
3000'-9000' (KB)	8.8-10.8	8 - 10 ml	32-42	LSND
9000-12760' (KB)	10.8-12.5	8-10 ml	40-60	LSND-Possible OBM

Sufficient mud material(s) to maintain mud properties, control lost circulation and contain a blowout will be available at the well site during drilling operations.

**6. Evaluation Program:**

Tests: No tests are currently planned.

Coring: No cores are currently planned.

Samples: No sampling is currently planned.

Logging

- Dual Induction – SFL /Gamma Ray/Caliper/SP/TDLT/CNL/ML  
TD to Base Surface Casing
- Cement Bond Log / Gamma Ray:  
TD to Base of Surface Casing or Top of Cement if below Base of Surface Casing

Stimulation: A stimulation or frac treatment will be designed for completion of this well based on openhole log analysis. The drill site, as approved, will be sufficient size to accommodate all completion activities.

**7. Abnormal Conditions:**

No abnormal temperatures or pressures are anticipated. No H<sub>2</sub>S has been encountered or known to exist from previous wells drilled to similar depths in the general area.

Maximum anticipated bottom hole pressure equals approximately 4078 psi (calculated at 0.52psi/foot of 2353 psi (anticipated bottom hole pressure minus the pressure of a partially evacuated hole calculated at 0.22 psi/foot of hole).



**8. Anticipated Starting Dates:**

- Anticipated Commencement Date- Within one year of APD issue.
- Drilling Days- Approximately 20 days
- Completion Days - Approximately 20 days
- Anticipate location construction within 30 days of permit issue.

**9. Variances:**

None anticipated

**10. Other:**

A Cultural Resource Inventory and Paleontology reconnaissance shall be conducted for the well location, access route and pipeline. The reports shall be submitted to the Division of Oil, Gas and Mining and the School and Institutional Trust lands Administration upon their receipt.

Inclination surveys will be run every 2000 feet to monitor hole angle.

# 2006-11 Enduring Archy Bench 10-22-34-36amd

## Casing Schematic

Surface

TOC @  
0.

w/198 washout ✓

9-5/8"  
MW 8.4  
Frac 19.3

Surface  
2016. MD

TOC @  
3271.

353' washout

TOC @  
5279.

w/128 washout  
propose to ± 1700' ✓

Intermediate  
9000. MD

7"  
MW 10.8  
Frac 19.3

✓ Adequate Due 12/7/07

4-1/2"  
MW 12.5

Production  
12760. MD

w/128 washout ✓

BOPE

Anticipated BHP = 4078 psi ???  
BHP Max =  $(12.5 \times 0.052)(12760) = 8294$  psi  
BHP Mod  $(0.22)(12760) = 2807$  psi  
MASP =  $8294 - 2807 = 5487$  psi

5m BOPE proposed

\* Adequate to divert and  
cycle out kick @ expected  
worst case scenario @ 12800 psi  
equivalent pressure  
may not be able to kill SI completely.

Well name:	<b>2006-11 Enduring Archy Bench 10-22-34-36amd</b>	
Operator:	<b>Enduring Resources, LLC</b>	
String type:	Surface	Project ID: 43-047-38605
Location:	Uintah County, Utah	

**Design parameters:**
**Collapse**

Mud weight: 8.400 ppg  
Design is based on evacuated pipe.

**Minimum design factors:**
**Collapse:**

Design factor 1.125

**Burst:**

Design factor 1.00

**Environment:**

H2S considered? No  
Surface temperature: 75 °F  
Bottom hole temperature: 103 °F  
Temperature gradient: 1.40 °F/100ft  
Minimum section length: 1,000 ft

Cement top: Surface

**Burst**

Max anticipated surface pressure: 1,774 psi  
Internal gradient: 0.120 psi/ft  
Calculated BHP 2,016 psi

No backup mud specified.

**Tension:**

8 Round STC: 1.80 (J)  
8 Round LTC: 1.80 (J)  
Buttress: 1.60 (J)  
Premium: 1.50 (J)  
Body yield: 1.60 (B)

Tension is based on buoyed weight.  
Neutral point: 1,765 ft

**Non-directional string.**
**Re subsequent strings:**

Next setting depth: 8,063 ft  
Next mud weight: 9.800 ppg  
Next setting BHP: 4,105 psi  
Fracture mud wt: 19.250 ppg  
Fracture depth: 2,016 ft  
Injection pressure: 2,016 psi

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Est. Cost (\$)
1	2016	9.625	36.00	J-55	ST&C	2016	2016	8.796	17523

Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (kips)	Tension Strength (kips)	Tension Design Factor
1	880	2020	2.296	2016	3520	1.75	63.6	394	6.20 J

Prepared Helen Sadik-Macdonald  
by: Div of Oil, Gas & Minerals

Phone: 801/538-5357  
FAX: 801/359-3940

Date: December 7, 2007  
Salt Lake City, Utah

**Remarks:**

Collapse is based on a vertical depth of 2016 ft, a mud weight of 8.4 ppg. The casing is considered to be evacuated for collapse purposes.  
Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

*Engineering responsibility for use of this design will be that of the purchaser.*

Well name:	<b>2006-11 Enduring Archy Bench 10-22-34-36amd</b>		
Operator:	<b>Enduring Resources, LLC</b>		
String type:	Intermediate	Project ID:	43-047-38605
Location:	Uintah County, Utah		

**Design parameters:**
**Collapse**

Mud weight: 10.800 ppg  
Internal fluid density: 2.330 ppg

**Minimum design factors:**
**Collapse:**

Design factor 1.125

**Burst:**

Design factor 1.00

**Environment:**

H2S considered? No  
Surface temperature: 75 °F  
Bottom hole temperature: 201 °F  
Temperature gradient: 1.40 °F/100ft  
Minimum section length: 1,000 ft

Cement top: 3,271 ft

**Burst**

Max anticipated surface pressure: 5,479 psi  
Internal gradient: 0.220 psi/ft  
Calculated BHP 7,459 psi

Annular backup: 2.33 ppg

**Tension:**

8 Round STC: 1.80 (J)  
8 Round LTC: 1.80 (J)  
Buttress: 1.60 (J)  
Premium: 1.50 (J)  
Body yield: 1.60 (B)

Tension is based on buoyed weight.  
Neutral point: 7,534 ft

**Non-directional string.**
**Re subsequent strings:**

Next setting depth: 12,760 ft  
Next mud weight: 12.500 ppg  
Next setting BHP: 8,286 psi  
Fracture mud wt: 19.250 ppg  
Fracture depth: 12,760 ft  
Injection pressure: 12,760 psi

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Est. Cost (\$)
1	9000	7	26.00	N-80	LT&C	9000	9000	6.151	80012

Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (kips)	Tension Strength (kips)	Tension Design Factor
1	3960	5410	1.366	6369	7240	1.14	195.9	519	2.65 J

Prepared Helen Sadik-Macdonald  
by: Div of Oil, Gas & Minerals

Phone: 801/538-5357  
FAX: 801/359-3940

Date: December 7, 2007  
Salt Lake City, Utah

**Remarks:**

Collapse is based on a vertical depth of 9000 ft, a mud weight of 10.8 ppg. An internal gradient of .121 psi/ft was used for collapse from TD. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

*Engineering responsibility for use of this design will be that of the purchaser.*

Well name:	<b>2006-11 Enduring Archy Bench 10-22-34-36amd</b>		
Operator:	<b>Enduring Resources, LLC</b>		
String type:	<b>Production</b>	Project ID:	<b>43-047-38605</b>
Location:	<b>Uintah County, Utah</b>		

**Design parameters:**
**Collapse**

Mud weight: 12.500 ppg  
Design is based on evacuated pipe.

**Minimum design factors:**
**Collapse:**

Design factor 1.125

**Burst:**

Design factor 1.00

**Environment:**

H2S considered? No  
Surface temperature: 75 °F  
Bottom hole temperature: 254 °F  
Temperature gradient: 1.40 °F/100ft  
Minimum section length: 1,000 ft

Cement top: 5,279 ft

**Burst**

Max anticipated surface pressure: 5,479 psi  
Internal gradient: 0.220 psi/ft  
Calculated BHP 8,286 psi

No backup mud specified.

**Tension:**

8 Round STC: 1.80 (J)  
8 Round LTC: 1.80 (J)  
Buttress: 1.60 (J)  
Premium: 1.50 (J)  
Body yield: 1.60 (B)

**Non-directional string.**

Tension is based on buoyed weight.  
Neutral point: 10,481 ft

Estimated cost: 63,023 (\$)

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Est. Cost (\$)
2	11800	4.5	13.50	N-80	LT&C	11800	11800	3.795	56541
1	960	4.5	15.10	HCL-80	LT&C	12760	12760	3.701	6482

Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (kips)	Tension Strength (kips)	Tension Design Factor
2	7662	8540	1.115	8075	9020	1.12	141.7	270	1.91 J
1	8286	12330	1.488	8286	10480	1.26	-17.6	325	-18.42 J

Prepared by: Helen Sadik-Macdonald  
Div of Oil, Gas & Minerals

Phone: 801/538-5357  
FAX: 801/359-3940

Date: December 7, 2007  
Salt Lake City, Utah

**Remarks:**

Collapse is based on a vertical depth of 12760 ft, a mud weight of 12.5 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

*Engineering responsibility for use of this design will be that of the purchaser.*

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: ML-49959
2. NAME OF OPERATOR: Enduring Resources, LLC		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: n/a
3. ADDRESS OF OPERATOR: 475 17th Street, Suite 1500 CITY Denver STATE CO ZIP 80202		7. UNIT or CA AGREEMENT NAME: n/a
PHONE NUMBER: (303) 350-5114		8. WELL NAME and NUMBER: Archy Bench 10-22-34-36
4. LOCATION OF WELL FOOTAGES AT SURFACE: 755' FSL - 2210' FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWSE 36 10S 22E S		9. API NUMBER: 4304738605
COUNTY: Uintah		10. FIELD AND POOL, OR WILDCAT: Undesignated
STATE: UTAH		

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: Request for APD Extension
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Enduring Resources, LLC respectfully request an extension to the expiration date of this Application for Permit to Drill ....

FROM: 5/14/2008  
TO: 5/14/2009

Approved by the  
Utah Division of  
Oil, Gas and Mining

COPY SENT TO OPERATOR

Date: 5.21.2008

Initials: KS

Date: 05-20-08  
By: [Signature]

NAME (PLEASE PRINT) Alvin (Al) Arlian

TITLE Landman - Regulatory Specialist

SIGNATURE [Signature]

DATE 5/12/2008

(This space for State use only)

RECEIVED

MAY 19 2008

DIV. OF OIL, GAS & MINING



**Application for Permit to Drill  
Request for Permit Extension  
Validation**

(this form should accompany the Sundry Notice requesting permit extension)

**API:** 4304738605  
**Well Name:** Archy Bench 10-22-34-36  
**Location:** 755' FSL - 2210' FELSWSE, Sec 36, T10S-R22E  
**Company Permit Issued to:** Enduring Resources, LLC  
**Date Original Permit Issued:** 5/14/2007

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision.

Following is a checklist of some items related to the application, which should be verified.

If located on private land, has the ownership changed, if so, has the surface agreement been updated? Yes ☐ No ☐

Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? Yes ☐ No ☒

Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? Yes ☐ No ☒

Have there been any changes to the access route including ownership, or right-of-way, which could affect the proposed location? Yes ☐ No ☒

Has the approved source of water for drilling changed? Yes ☐ No ☒

Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? Yes ☐ No ☒

Is bonding still in place, which covers this proposed well? Yes ☒ No ☐

  
Signature

5/12/2008  
Date

Title: Landman - Regulatory Specialist

Representing: Enduring Resources, LLC

RECEIVED

MAY 19 2008

DIV. OF OIL, GAS & MINING

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

**CONFIDENTIAL**

FORM 9

**SUNDRY NOTICES AND REPORTS ON WELLS**

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL

OIL WELL ☐

GAS WELL ☒

OTHER \_\_\_\_\_

2. NAME OF OPERATOR:

Enduring Resources, LLC

3. ADDRESS OF OPERATOR:

475 17th Street, Suite 1500 CITY Denver

STATE CO ZIP 80202

PHONE NUMBER:

(303) 350-5114

5. LEASE DESIGNATION AND SERIAL NUMBER:

ML-49959

6. IF INDIAN, ALLOTTEE OR TRIBE NAME:

n/a

7. UNIT or CA AGREEMENT NAME:

n/a

8. WELL NAME and NUMBER:

Archy Bench 10-22-34-36

9. API NUMBER:

4304738605

10. FIELD AND POOL, OR WILDCAT:

Undesignated

4. LOCATION OF WELL

FOOTAGES AT SURFACE: 755' FSL - 2210' FEL

COUNTY: Uintah

QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWSE 36 10S 22E S

STATE:

UTAH


11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: Request for APD Extension
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Enduring Resources, LLC respectfully requests a one year extension of the expiration date of this Application for Permit to Drill.

Approved by the  
Utah Division of  
Oil, Gas and Mining

Date: 05-18-09  
By: 

COPY SENT TO OPERATOR

Date: 5.19.2009

Initials: KS

NAME (PLEASE PRINT) Alvin (Al) Arlian

TITLE Landman - Regulatory Specialist

SIGNATURE 

DATE 5/11/2009

(This space for State use only)

RECEIVED

MAY 18 2009

DIV. OF OIL, GAS & MINING



**Application for Permit to Drill  
Request for Permit Extension  
Validation**

(this form should accompany the Sundry Notice requesting permit extension)

**API:** 4304738605  
**Well Name:** Archy Bench 10-22-34-36  
**Location:** 755' FSL - 2210' FELSWSE, Sec 36, T10S-R22E  
**Company Permit Issued to:** Enduring Resources, LLC  
**Date Original Permit Issued:** 5/14/2007

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision.

Following is a checklist of some items related to the application, which should be verified.

If located on private land, has the ownership changed, if so, has the surface agreement been updated? Yes ☐ No ☐

Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? Yes ☐ No ☒

Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? Yes ☐ No ☒

Have there been any changes to the access route including ownership, or right-of-way, which could affect the proposed location? Yes ☐ No ☒

Has the approved source of water for drilling changed? Yes ☐ No ☒

Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? Yes ☐ No ☒

Is bonding still in place, which covers this proposed well? Yes ☒ No ☐

  
Signature

5/11/2009

Date

Title: Administrative Assistant

Representing: Enduring Resources, LLC

**RECEIVED**

**MAY 18 2009**

**DIV. OF OIL, GAS & MINING**



GARY R. HERBERT  
Governor

GREGORY S. BELL  
Lieutenant Governor

# State of Utah

## DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER  
Executive Director

### Division of Oil, Gas and Mining

JOHN R. BAZA  
Division Director

May 25, 2010

Al Arlian  
Enduring Resources, LLC  
475 17<sup>TH</sup> Street Ste 1500  
Denver, CO 80202

Re: APD Rescinded – Archy Bench 10-22-34-36, Sec. 36 T.10S, R. 22E  
Uintah County, Utah API No. 43-047-38605

Dear Mr. Arlian:

The Application for Permit to Drill (APD) for the subject well was approved by the Division of Oil, Gas and Mining (Division) on May 14, 2007. On May 20, 2008 and May 18, 2009 the Division granted a one-year APD extension. No drilling activity at this location has been reported to the division. Therefore, approval to drill the well is hereby rescinded, effective May 25, 2010.

If any previously unreported operations have been performed on this well location, it is imperative that you notify the Division immediately.

Sincerely,

Diana Mason  
Environmental Scientist

cc: Well File  
SITLA, Ed Bonner